



BILL OF QUANTITIES		
MATERIAL	20ft QTY	40ft QTY
NON-WOVEN GEOTEXTILE FILTER CLOTH	2M x 7M (14M ²)	2M x 13M (26M ²)
ROAD CRUSH - CORAL / CRUSHED STONE (DUST TO APPROX 20mm DIAMETER)	2.5M ² (4 TONNES)	4M ² (7 TONNES)
FORM WORK BOARDS (25MM x 200MM)	30M	55M
SL72 MESH (7mm @ 200mm)	7M x 1M (7M)	13M x 1M (13M ²)
CONCRETE (C25)	2.5 (5 TONNES)	4M ² (9.5 TONNES)

- NOTE:
- EXCAVATE AREA DOWN 250MM & LEVEL SURFACE.
 - LAY ROAD CRUSH IN 50MM LAYERS AND COMPACT EACH LAYER WITH MECHANICAL VIBRATORY
 - INSTALL SL75 STEEL MESH 75MM BELOW CONCRETE SURFACE
 - C25 (25MPa) CONCRET RATIO:
1 (CEMENT) : 2 (SAND) : 3 (AGGREGATE)

20' / 40' CONTAINER FOUNDATION			
REVISION:	DRAFT (V0.1)	DATE:	20/02/2025